



NOTES:

1. SIGN MATERIALS, CONSTRUCTION AND PLACEMENT SHALL BE IN CONFORMANCE WITH THE MOST RECENT EDITION OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES AND SECTION 215 OF THE STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION.
2. SET CENTER OF SIGN POLE BETWEEN 12 AND 24 INCHES FROM THE BACK OF SIDEWALK.
3. STOP SIGN 30" MINIMUM, PLACED 7'-0" FROM GRADE.
4. SIGN POST SHALL NOT BE ANCHORED IN SIDEWALK, DIRECT BURY OR OPTIONAL BREAK AWAY MODEL CAN BE USED WITH SLIGHT BASE MODIFICATION.
5. IF CONCRETE COLLAR IS WITHIN 6 INCHES OF THE SIDEWALK CONNECT TO SIDEWALK.



TOWN OF GARDNERVILLE

TOWN ROAD  
DECORATIVE SIGN

SECTION:

DATE: 3/11/13

DWG: TOG-03